

ACHIZIToare:

OBIECTIV: CABLARE STRUCTURATA INTERIOR CLADIRI USAMV CLUJ

**DEVIZ OFERTA**

Nr.crt.	Capitolul de lucrari	UM	Cantitate	Pret unitar	
				a) Material b) Manopera c) Utilaj d) Transport Total (a+b+c+d) (lei/UM)	Valoare: Material (3x4a) Manopera (3x4b) Utilaj (3x4c) Transport (3x4d) Total (5+6+7+8) (lei)
Sectiune tehnica				Sectiune financiara	
0	1	2	3	4	5-9

1.	Pozare cablu UTP cat. 6 (cu canal pvc de cablu 60x40 mm)	ML	5500		
2.	Montare aparent prize duble RJ-45 cat. 6	BUC	120		
3.	Montare si cablare patch panel cat.6 in rack	PORT	120		
4.	Montare si echipare rack 6U cu unitate PDU 6 prize si organizator cabluri	BUC	10.0		
5.	Sertizari mufe UTP cat.6	BUC	240.00		
6.	Strapungere pereti ( diametru gaura 10 - 16 mm)	BUC	100		

0	1	2	3	4	5-9
7.	Montare si configurare switch cu management L3 24p x100/1000Mbps + 2p x1G/10G SFP	BUC	7		
8.	Montare si configurare AP wireless de interior dual-band 2.4/5Ghz, a/bgn	BUC	7		

9. **Cheltuieli directe** :

- a. Materiale = lei ;
- b. Manopera = lei;
- c. C.A.S : % = lei ;
- d. Somaj: % = lei ;
- e. Sanatate : % = lei ;
- f. Accidente : % = lei ;

**Total cheltuieli directe** = a+b+c+d+e+f = lei .

10. **Cheltuieli indirecte** : % = lei ;

11. **Profit** : % = lei ;

12. **TOTAL GENERAL** = Lei .

Preturile sunt fara TVA inclus.